

ADDENDUM NO. 1

to **CONTRACT DOCUMENTS** for

Treatment Plant Site Improvements – Access Roadway Modifications
Project No. WA5096
Grants Pass, Oregon 97526

To All Planholders:

The following changes, additions, and/or deletions are hereby made a part of the Contract Documents for the construction of the Treatment Plant Site Improvements – Access Roadway Modifications; Project No. WA5096, Grants Pass, Oregon, as fully and completely as if the same were fully set forth therein:

1. ON THE CONSTRUCTION PLANS...

Sheet C-1:

- **Replace** all references to “Curb & Gutter” **with** “Curb”.
- **Remove** Site Plan Note “**Furnish & Install Key Pad Conduit**”.
- **Replace** Site Plan Note “ReGrade Slope above New Curb to Approx. 1H:1V, Surface with 2” of 2” Round Rock” **with** “**ReGrade Slope above New Curb to Approx. 2H:1V, Surface with Topsoil**”.

Sheet C-1 – Note No. 3:

- **Replace** “2” Dense HMAC” **with** “1/2” Dense HMAC”.

Sheet C-2:

- **Replace** all references to “Curb & Gutter” **with** “Curb”. A Clarification, Section B on Sheet C-2 is to be shown as on Sheet C-3

2. IN THE CONTRACT DOCUMENTS...

- **Change** the quantity for Bid Item No. 8 (**¾”-0 Aggregate Base**) from “27 CY” **to** “**31 CY**”.
- **Change** the quantity for Bid Item No. 9 (**Level 2, ½” Dense, MHMAC Mixture**) from “23 TN” **to** “**26 TN**”.
- **Change** the quantity for Bid Item No.11 (**Concrete Curbs, Curb and Gutter**) from 55 FT **to** “**90 FT**”.

3. CLARIFICATIONS...

- Project to be **bid and paid** at prevailing wage rates regardless of contract amount.
- Contractor to coordinate with City of Grants Pass (Owner) for location and capping of irrigation.
- Location of Curb & Gutter on North End of Parking Lot to be clarified at time of construction.

ATTACHED ARE REVISED PAGES OF THE BID PROPOSAL. PLEASE USE THESE REPLACEMENT PAGES WHEN SUBMITTING YOUR BID.

Also included in Addendum No. 1: **Mandatory Pre-Bid Meeting List**

All Bidders shall acknowledge receipt and acceptance of this Addendum No. 1 by signing in the space provided and submitting the signed Addendum with the bid. Bids submitted without this Addendum will be considered irregular and may not be accepted.

RECEIPT OF THIS ADDENDUM IS ACKNOWLEDGED AND CONDITIONS ARE

HEREBY AGREED TO THIS ____ DAY OF _____ 2013.

Bidder's Name (Company)

BY:

(Signature)

BID SCHEDULE

**Water Treatment Plant Improvements – Access Roadway Modifications;
Project No. WA5096**

Item	Quantity	Unit	Unit Price (Fig.)	Extended Amount
PART 00200 – TEMPORARY FEATURES AND APPURTENANCES				
1	Mobilization , move in of equipment and materials per APWA/ODOT Sec. 00210.			
	1	LS	\$	\$
2	Work Zone Traffic Control, Complete , per approved plans, TCP, M.U.T.C.D. and APWA/ODOT Sec. 00225 and 00225.90(b).			
	1	LS	\$	\$
3	Inlet Protection , per approved plans and APWA/ODOT Sec. 00280.10(a).			
	1	EA	\$	\$
4	Pollution Control Plan , per APWA/ODOT Sec. 00290.30(b).			
	1	LS	\$	\$
PART 00300 – ROADWORK				
5	Removal of Structures and Obstructions , per approved plans and APWA/ODOT Sec. 00310. Includes sections of curb, gutter and sidewalk.			
	1	LS	\$	\$
6	Clearing and Grubbing , per approved plans and APWA/ODOT Sec. 00320. Includes all vegetation marked for removal and stump grinding where necessary.			
	1	LS	\$	\$
7	General Excavation , to establish subgrade for all work and cut slopes, per approved plans and APWA/ODOT Sec.00330.			
	144	CY	\$	\$
PART 00600 – BASES				
8	¾”-0 Aggregate Base , for installation of asphalt, curb, gutter and sidewalk, per APWA/ODOT Sec. 00641, installed.			
	31	CY	\$	\$
PART 00700 – WEARING SURFACES				
9	Level 2, ½” Dense, MHMAC Mixture , Varied Compacted Thickness, per approved plans and APWA/ODOT Sec. 00744, installed.			
	26	TN	\$	\$
10	Concrete Curbs, Standard Curb , per approved plans, GPSD #102 (Type "C") and APWA/ODOT Sec. 00759, installed.			
	136	FT	\$	\$

11	Concrete Curbs, Curb and Gutter , per approved plans, GPSD #102 (Type "A") and APWA/ODOT Sec. 00759, installed.		
	90	FT	\$
PART 01000 – RIGHT OF WAY DEVELOPMENT AND CONTROL			
12	Topsoil , furnishing and placement of imported topsoil, per approved plans and APWA/ODOT Sec. 01040, installed.		
	21	CY	\$
13	Removing and Rebuilding Fence , per approved plans and APWA/ODOT Sec. 01050, installed.		
	20	FT	\$
14	Chain Link Cantilever Slide Gate , removal of existing swing gate, keypad and appurtenances, furnishing and installing all labor and materials for operation of new chain link cantilever slide gate, complete, per approved plans and Special Provisions Sec. 01050.		
	1	LS	\$
PART 00200 – TEMPORARY FEATURES AND APPURTENANCES			\$
PART 00300 – ROADWORK			\$
PART 00600 – BASES			\$
PART 00700 – WEARING SURFACES			\$
PART 01000 – RIGHT OF WAY DEVELOPMENT AND CONTROL			\$
TOTAL:			\$
CONTRACTOR SIGNATURE:			
DATE:			

ATTENDANCE LIST

Project Name/Number: WTP Access Road Modifications / WA-5096	Date: 3/07/2013
Location: Water Treatment Plant - 821 SE "M" Street (10:00 a.m.)	
Owner: City of Grants Pass	Engineer/Architect: Murray, Smith & Associates, Inc.
Contracting Agency:	
Contractor's Name:	
MANDATORY PRE-BID <input checked="" type="checkbox"/> BID <input type="checkbox"/> PRECONSTRUCTION <input type="checkbox"/>	

Name	Agency	Phone No./ Mobile No.	Email Address	Signature
1. John Deery	COGP	905-2079		John Deery
2. Bob Smith	Grants Pass	541-600-5102		Bob Smith
3. Tom Smith	Grants Pass	541-600-5102		Tom Smith
4. Joe Smith	Grants Pass	950-8700		Joe Smith
5. Marty Vesika	Assessment	226-6237	NOVIKA @ ASSASSESSMENT.COM	Marty Vesika
6. Nancy Murray	City of G.P.	450-6063		Nancy Murray
7. Bacey Peterson	Grants Pass	541-600-4873		Bacey Peterson
8. Ray Ortega	Taylorville Dam, Inc	541-779-3565	road.maint@tdi.com	Ray Ortega
9. Stephen Smith	Grants Pass	541-600-5102		Stephen Smith
10. Steve Hush	Grants Pass LLC	541-476-1111	Steve@grantspass.com	Steve Hush
11. James Conway	City of Grants Pass	541-450-6119		James Conway
12. Chris Kummer	City of Grants Pass	541-450-6118		Chris Kummer
13. Bigelow Robert	Robert, Inc.	541-600-3350	Robert@robertinc.com	Bigelow Robert
14.				
15.				
16.				

END OF ADDENDUM NO. 1