



General Note:

1. Valve box not to rest on operating assembly.
2. Center valve box on axis of operator nut.
3. Valves 12" and smaller shall be provided with compacted aggr. base on undisturbed ground. Valves greater than 12" shall be installed on precast concrete block, (4" thick).
4. Welds shall be minimum 1/4" all around.
5. Hot dip galvanize operator extension after fabrication.
6. Casting shall meet H20 load requirement.
7. See project plans for details not shown.
8. Water valve boxes and operator nut assemblies not installed within these tolerances will be reset by the city at the contractor's expense

The selection and use of this standard drawing, while designed in accordance with generally accepted engineering principles and practices, is the sole responsibility of the user.

Designed By: STAFF
 Drawn By: KJD
 Checked By: MPT
 Approved: JMC



CITY OF GRANTS PASS
 101 Northwest 'A' Street
 Grants Pass, OR 97526
 (541) 450-6060 ph (541) 476-9218 fax

No.	Date	Revisions	App. By

VALVE BOX AND OPERATOR EXTENSION ASSEMBLY

2018
 DWG. NO. GP258