

**ADDENDUM NO. 1**

to **CONTRACT DOCUMENTS** for

"B" Street Sidewalk Infill  
Project No. TR6118  
Grants Pass, Oregon 97526

To All Plan Holders:

The following changes, additions, and/or deletions are hereby made a part of the Contract Documents for the construction of the "B" Street Sidewalk Infill Project No. TR6118, Grants Pass, Oregon, as fully and completely as if the same were fully set forth therein:

**1. ON THE CONSTRUCTION PLANS...**

- On Sheets 2 and 3 of the Construction Drawings:
  - Revise Note 16 to read "Install Monolithic Sidewalk Retaining Wall, See Detail **Sheet 11** or Retaining Wall with Footing per Sheet 4 (Depending on Height of Wall). Match Height (Top) of Wall to Ground Level."

**2. IN THE CONTRACT DOCUMENTS...**

**Bid Proposal - Bid Schedule - Phase 1: - The following bid item has been added.**

<b>4</b>	<b>Flagging Hours, APWA/ODOT Sec. 00225.97 (a)</b>			
	<b>200</b>	<b>HRS</b>	<b>\$52.00</b>	<b>\$10,400.00</b>

**Bid Proposal - Bid Schedule - Entire Project: - The following bid item has been added.**

<b>4</b>	<b>Flagging Hours, APWA/ODOT Sec. 00225.97 (a)</b>			
	<b>400</b>	<b>HRS</b>	<b>\$52.00</b>	<b>\$20,800.00</b>

**3. CLARIFICATIONS...**

- The City of Grants Pass has determined that in the public interest, in the interest of prospective bidders, and in the interest of the best practices for *Public Improvement Competitive Bidding*, to solicit Bid Proposals for **both** the "**B**" **Street Sidewalk Infill - Phase 1**, and the "**B**" **Street Sidewalk Infill - Entire Project**. Prospective Bidders will need to complete the Bid Schedules for **both** Phase 1 and Entire Project.

- The City of Grants Pass desires to perform the work for the Entire Project. However, the City reserves the right to award the Entire Project, or to award Phase 1, or to reject any or all bids upon a finding it is in the public interest to do so. Depending on the Bid Schedule (Phase 1 or Entire Project) the City determines to award; the City will reject all bids for the non-selected Bid Schedule, and award the project to the lowest responsible bidder for the selected Bid Schedule.
- Bid opening date will remain **Thursday, February 25, 2021 at 3:00pm.**
- Regarding the slope in question at 655 NW B Street: Bid as proposed.

**ATTACHED ARE THE FOLLOWING:**

- REVISED PAGES OF THE BID SCHEDULE (8 PAGES)

**PLEASE USE THESE REPLACEMENT PAGES WHEN SUBMITTING YOUR BID.**

All Bidders shall acknowledge receipt and acceptance of this Addendum No. 1 by signing in the space provided and submitting the signed Addendum with the bid. Bids submitted without this Addendum will be considered irregular and may not be accepted.

RECEIPT OF THIS ADDENDUM IS ACKNOWLEDGED AND CONDITIONS ARE HEREBY

AGREED TO THIS \_\_\_\_\_ DAY OF \_\_\_\_\_ 2021.

\_\_\_\_\_  
Bidder's Name (Company)

BY: \_\_\_\_\_  
(Signature)

**END OF ADDENDUM**

**BID SCHEDULE**  
**“B” Street Sidewalk Infill - Phase 1**  
**TR6118**

<b>PART 00200 – TEMPORARY FEATURES AND APPURTENANCES</b>				
<b>Item</b>	<b>Quantity</b>	<b>Unit</b>	<b>Unit Price (Fig.)</b>	<b>Extended Amount</b>
<b>1</b>	<b>Mobilization</b> , move in of equipment and materials per APWA/ODOT Sec. 00210, complete.			
	1	LS	\$	\$
<b>2</b>	<b>Work Zone Traffic Control</b> , includes TCD, TCM and TCP per approved plans, M.U.T.C.D., and APWA/ODOT Sec. 00225 and 00225.90 (b), complete.			
	1	LS	\$	\$
<b>3</b>	<b>Erosion &amp; Sediment Control</b> , per approved plans and APWA/ODOT Sec. 00280.00 Inlet Protection, Dust Control, Sediment Fence, Biofilter Bags, installed complete.			
	1	LS	\$	\$
<b>4</b>	<b>Flagging Hours</b> , APWA/ODOT Sec. 00225.97 (a)			
	200	HRS	\$52.00	\$10,400.00
<b>5</b>	<b>Construction Staking</b> , lay out and set construction stakes and marks to establish the lines, grades, and slopes necessary for project completion, per Special Provisions Sec. 00150.15 (c).			
	1	LS	\$	\$
<b>PART 00300 – ROADWORK</b>				
<b>6</b>	<b>Removal of Structures and Obstructions</b> , includes removal and proper disposal of existing pipe, per approved plans and APWA/ODOT Sec. 00310.and 00291.20(c), (Hazardous Waste), complete.			
	1	LS	\$	\$
<b>7</b>	<b>Clearing and Grubbing</b> , per approved plans and APWA/ODOT Sec. 00320, including all vegetation, trees, Pacific Power wood remains and stumps marked for removal. Also included is air/pneumatic soil excavation to be performed by an ISA arborist.			
	1	LS	\$	\$
<b>8</b>	<b>Relocate Private Valves, RP's, DCV's etc. Behind Sidewalk</b> , per approved plans and current plumbing code. Includes excavation and plumbing permits.			
	13	EA	\$	\$
<b>9</b>	<b>Adjust Water Meter Boxes</b> , per approved plans and APWA/ODOT Sec. 00490.48. Includes installation of City provided meter boxes, adjustment to grade and excavation.			
	15	EA	\$	\$
<b>PART 00400 – DRAINAGE AND SEWERS</b>				
<b>10</b>	<b>Connect Existing Storm Drain Pipe Through Curb</b> , per approved plans and APWA/ODOT Sec. 00445. Includes all connections to existing storm drain, pipe, trench excavation, sawcutting, concrete, bedding and compacted backfill per GP300 and APWA/ODOT Sec.00405, installed complete.			
	7	EA	\$	\$
<b>11</b>	<b>Landscape Sleeves</b> , per approved plans and APWA/ODOT Section 01120.11. Installed, complete.			
	11	EA	\$	\$

12	<b>Install 12" Storm Drain Pipe, PVC 3034</b> , per approved plans and APWA/ODOT Sec. 00445. Includes trench excavation, bedding and compacted backfill per APWA/ODOT Sec.00405, installed complete.			
	18	LF	\$	\$
13	<b>Concrete Inlet, Type "B"</b> , per GP371, approved plans and APWA/ODOT Sec. 00470.			
	4	EA	\$	\$
14	<b>Connect Existing Storm Drain to New Storm Drain</b> , per approved plans and APWA/ODOT Sec. 00445. Includes all connections to existing storm drain, pipe, trench excavation, sawcutting, concrete, bedding and compacted backfill per GP300 and APWA/ODOT Sec.00405, installed complete.			
	3	EA	\$	\$
<b>PART 00600 – BASES</b>				
15	<b>Aggregate Base Course (Driveway)</b> , Varying thickness of ¾"-0 aggregate, compacted in place, per approved plans and APWA/ODOT Section 00640, 00641 and 02630. Installed complete for gravel driveway transitions.			
	16	TN	\$	\$
<b>PART 00700 – WEARING SURFACES</b>				
16	<b>Asphalt Pavement Patch</b> , ½" dense, Level 2 mix, 3" compacted thickness, per APWA/ODOT Section 00744. Includes sawcutting, pavement removal, excavation, base rock, any minor valve or manhole adjustments. Installed complete.			
	49	TN	\$	\$
17	<b>Asphalt Pavement (Driveway)</b> , ½" dense, Level 2 mix, 2" compacted thickness, per APWA/ODOT Section 00744. Includes sawcutting, pavement removal, excavation, base rock, gravel transition to existing driveway, any minor valve or manhole adjustments. Installed complete.			
	13	TN	\$	\$
18	<b>Concrete Curb &amp; Gutter, Type "A" (Match Existing)</b> , per approved plans, GP700 and APWA/ODOT Sec. 00759. Includes sawcutting, curb and gutter removal, excavation, base rock, installed complete.			
	793	LF	\$	\$
19	<b>Concrete Sidewalk</b> , per approved plans, GP720 and APWA/ODOT Sec. 00759. Includes excavation, base rock, signage sleeves, installed complete.			
	7,250	SF	\$	\$
20	<b>Concrete Sidewalk Ramp with Truncated Domes (Yellow)</b> , per approved plans, GP756 and APWA/ODOT Section 00759, (ERD755). Includes sawcutting, removal of curb and gutter, excavation, base rock, concrete flatwork, truncated domes, curb and gutter, signage sleeves and raising existing manholes, installed complete.			
	1,905	SF	\$	\$
21	<b>Concrete Residential Driveway Apron</b> , per approved plans, GP740, GP745, GP750 and APWA/ODOT Section 00759. Includes sawcutting, pavement removal, excavation, base rock, weep holes, installed complete.			
	2,416	SF	\$	\$
22	<b>Concrete Pavement (Driveway)</b> , per approved plans and APWA/ODOT Section 00759. Includes sawcutting, pavement removal, excavation, base rock, any minor valve or manhole adjustments. Installed complete.			
	78	SF	\$	\$

PART 01000 – RIGHT OF WAY DEVELOPMENT AND CONTROL				
23	<b>Remove and Replace Fence</b> , remove and replace all existing fence identified on the plans with new fence to match existing, per approved plans and APWA/ODOT Section 01050. Installed, complete.			
	1	LS	\$	\$
24	<b>Landscape Restoration</b> , restore existing landscaping, including, but not limited to imported topsoil placement, reseeding of disturbed areas and irrigation repair, per approved plans and APWA/ODOT Section 01030, Section 01040 and Section 01120. Installed complete.			
	1	LS	\$	\$
25	<b>Maackia Amurensis “Amur Maackia”, 6’ Height with 1.5” Caliper</b> , per approved plans, landscape documents and specifications, and APWA/ODOT Section 01030 and 01040. Includes watering bags. Installed complete and established.			
	5	EA	\$	\$
26	<b>Pistachia Chinensis “Chinese Pistache”, 6’ Height with 1.5” Caliper</b> , per approved plans, landscape documents and specifications, and APWA/ODOT Section 01030 and 01040. Includes watering bags. Installed complete and established.			
	5	EA	\$	\$
27	<b>Install Single Mailbox Supports and Mailboxes</b> , remove and replace existing mailboxes, per approved plans, GP100, and APWA/ODOT Section 01070. Installed complete. Temporarily mount during construction.			
	1	EA	\$	\$
28	<b>Install Pedestrian Stairway with Handrails Per Detail 1 (902 NW B ST)</b> , remove and replace existing stairway, per approved plans, ODOT Standard Drawing RD770, RD771, and APWA/ODOT Section 00759 and Section 00810. Includes sawcutting, stairway removal, excavation, base rock, weep holes, installed complete.			
	1	LS	\$	\$
29	<b>Install Pedestrian Stairway Per Detail 2 (620 NW B ST)</b> , remove and replace existing stairway, per approved plans and APWA/ODOT Section 759. Includes sawcutting, stairway removal, excavation, base rock, weep holes, installed complete.			
	1	LS	\$	\$
30	<b>Install Pedestrian Stairway Per Detail 3 (614 NW B ST)</b> , remove and replace existing stairway, per approved plans and APWA/ODOT Section 759. Includes sawcutting, stairway removal, excavation, base rock, weep holes, installed complete.			
	1	LS	\$	\$
31	<b>Install Pedestrian Stairway Per Detail 4 (619 NW B ST)</b> , remove and replace existing stairway, per approved plans and APWA/ODOT Section 759. Includes sawcutting, stairway removal, excavation, base rock, weep holes, installed complete.			
	1	LS	\$	\$
32	<b>Install Pedestrian Stairway Per Detail 5 (613 NW B ST)</b> , remove and replace existing stairway, per approved plans and APWA/ODOT Section 759. Includes sawcutting, stairway removal, excavation, base rock, weep holes, installed complete.			
	1	LS	\$	\$
33	<b>Monolithic Retaining Wall</b> , monolithic concrete retaining wall at back of sidewalk, per approved plans and APWA/ODOT Section 00759. Includes excavation, backfill installed complete.			
	360	SF	\$	\$
34	<b>Retaining Wall with Footing</b> , monolithic concrete retaining wall at back of sidewalk, per approved plans and APWA/ODOT Section 00759. Includes excavation, backfill installed complete.			
	930	SF	\$	\$

<b>PART 00200 – TEMPORARY FEATURES AND APPURTENANCES</b>	<b>\$</b>
<b>PART 00300 – ROADWORK</b>	<b>\$</b>
<b>PART 00400 – DRAINAGE AND SEWERS</b>	<b>\$</b>
<b>PART 00600 – BASES</b>	<b>\$</b>
<b>PART 00700 – WEARING SURFACES</b>	<b>\$</b>
<b>PART 01000 – RIGHT OF WAY DEVELOPMENT AND CONTROL</b>	<b>\$</b>
<b>SUM OF EXTENDED TOTALS</b>	<b>\$</b>

<b>CONTRACTOR SIGNATURE:</b>	
<b>DATE:</b>	

**BID SCHEDULE**  
**“B” Street Sidewalk Infill - Entire Project**  
**TR6118**

<b>PART 00200 – TEMPORARY FEATURES AND APPURTENANCES</b>				
<b>Item</b>	<b>Quantity</b>	<b>Unit</b>	<b>Unit Price (Fig.)</b>	<b>Extended Amount</b>
<b>1</b>	<b>Mobilization</b> , move in of equipment and materials per APWA/ODOT Sec. 00210, complete.			
	1	LS	\$	\$
<b>2</b>	<b>Work Zone Traffic Control, includes TCD, TCM and TCP</b> per approved plans, M.U.T.C.D., and APWA/ODOT Sec. 00225 and 00225.90 (b), complete.			
	1	LS	\$	\$
<b>3</b>	<b>Erosion &amp; Sediment Control</b> , per approved plans and APWA/ODOT Sec. 00280.00 Inlet Protection, Dust Control, Sediment Fence, Biofilter Bags, installed complete.			
	1	LS	\$	\$
<b>4</b>	<b>Flagging Hours</b> , APWA/ODOT Sec. 00225.97 (a)			
	400	HRS	\$52.00	\$20,800.00
<b>5</b>	<b>Construction Staking</b> , lay out and set construction stakes and marks to establish the lines, grades, and slopes necessary for project completion, per Special Provisions Sec. 00150.15 (c).			
	1	LS	\$	\$
<b>PART 00300 – ROADWORK</b>				
<b>6</b>	<b>Removal of Structures and Obstructions</b> , includes removal and proper disposal of existing pipe, per approved plans and APWA/ODOT Sec. 00310.and 00291.20(c), (Hazardous Waste), complete.			
	1	LS	\$	\$
<b>7</b>	<b>Clearing and Grubbing</b> , per approved plans and APWA/ODOT Sec. 00320, including all vegetation, trees, Pacific Power wood remains and stumps marked for removal. Also included is air/pneumatic soil excavation to be performed by an ISA arborist.			
	1	LS	\$	\$
<b>8</b>	<b>Relocate Private Valves, RP's, DCV's etc. Behind Sidewalk</b> , per approved plans and current plumbing code. Includes excavation and plumbing permits.			
	24	EA	\$	\$
<b>9</b>	<b>Licensed Plumber to Connect Existing Water Service to New Meters</b> , per approved plans and current plumbing code. Includes excavation, relocation of customer valves and plumbing permits.			
	3	EA	\$	\$
<b>10</b>	<b>Adjust Water Meter Boxes</b> , per approved plans and APWA/ODOT Sec. 00490.48. Includes installation of City provided meter boxes, adjustment to grade and excavation.			
	31	EA	\$	\$
<b>PART 00400 – DRAINAGE AND SEWERS</b>				
<b>11</b>	<b>Connect Existing Storm Drain Pipe Through Curb</b> , per approved plans and APWA/ODOT Sec. 00445. Includes all connections to existing storm drain, pipe, trench excavation, sawcutting, concrete, bedding and compacted backfill per GP300 and APWA/ODOT Sec.00405, installed complete.			
	14	EA	\$	\$

12	<b>Landscape Sleeves</b> , per approved plans and APWA/ODOT Section 01120.11. Installed, complete.			
	12	EA	\$	\$
13	<b>Install 12" Storm Drain Pipe, PVC 3034</b> , per approved plans and APWA/ODOT Sec. 00445. Includes trench excavation, bedding and compacted backfill per APWA/ODOT Sec.00405, installed complete.			
	41	LF	\$	\$
14	<b>Concrete Inlet, Type "B"</b> , per GP371, approved plans and APWA/ODOT Sec. 00470.			
	6	EA	\$	\$
15	<b>Connect Existing Storm Drain to New Storm Drain</b> , per approved plans and APWA/ODOT Sec. 00445. Includes all connections to existing storm drain, pipe, trench excavation, sawcutting, concrete, bedding and compacted backfill per GP300 and APWA/ODOT Sec.00405, installed complete.			
	5	EA	\$	\$
<b>PART 00600 – BASES</b>				
16	<b>Aggregate Base Course (Driveway)</b> , Varying thickness of ¾"-0 aggregate, compacted in place, per approved plans and APWA/ODOT Section 00640, 00641 and 02630. Installed complete for gravel driveway transitions.			
	16	TN	\$	\$
<b>PART 00700 – WEARING SURFACES</b>				
17	<b>Asphalt Pavement Patch</b> , ½" dense, Level 2 mix, 3" compacted thickness, per APWA/ODOT Section 00744. Includes sawcutting, pavement removal, excavation, base rock, any minor valve or manhole adjustments. Installed complete.			
	78	TN	\$	\$
18	<b>Asphalt Pavement (Driveway)</b> , ½" dense, Level 2 mix, 2" compacted thickness, per APWA/ODOT Section 00744. Includes sawcutting, pavement removal, excavation, base rock, gravel transition to existing driveway, any minor valve or manhole adjustments. Installed complete.			
	16	TN	\$	\$
19	<b>Concrete Curb &amp; Gutter, Type "A" (Match Existing)</b> , per approved plans, GP700 and APWA/ODOT Sec. 00759. Includes sawcutting, curb and gutter removal, excavation, base rock, installed complete.			
	1,196	LF	\$	\$
20	<b>Concrete Sidewalk</b> , per approved plans, GP720 and APWA/ODOT Sec. 00759. Includes excavation, base rock, signage sleeves, installed complete.			
	11,335	SF	\$	\$
21	<b>Concrete Sidewalk Ramp with Truncated Domes (Yellow)</b> , per approved plans, GP756 and APWA/ODOT Section 00759, (ERD755). Includes sawcutting, removal of curb and gutter, excavation, base rock, concrete flatwork, truncated domes, curb and gutter, raising existing manholes and signage sleeves, installed complete.			
	3,497	SF	\$	\$
22	<b>Concrete Residential Driveway Apron</b> , per approved plans, GP740, GP745, GP750 and APWA/ODOT Section 00759. Includes sawcutting, pavement removal, excavation, base rock, weep holes, installed complete.			
	3,862	SF	\$	\$
23	<b>Concrete Pavement (Driveway)</b> , per approved plans and APWA/ODOT Section 00759. Includes sawcutting, pavement removal, excavation, base rock, any minor valve or manhole adjustments. Installed complete.			
	776	SF	\$	\$



24	<b>Concrete Street Valley Gutter (Match Existing)</b> , per approved plans, GP702 and APWA/ODOT Section 00759. Includes sawcutting, curb and gutter removal, excavation, base rock, installed complete.		
	180	SF	\$
<b>PART 01000 – RIGHT OF WAY DEVELOPMENT AND CONTROL</b>			
25	<b>Remove and Replace Fence</b> , remove and replace all existing fence identified on the plans with new fence to match existing, per approved plans and APWA/ODOT Section 01050. Installed, complete.		
	1	LS	\$
26	<b>Landscape Restoration</b> , restore existing landscaping, including, but not limited to imported topsoil placement, reseeding of disturbed areas and irrigation repair, per approved plans and APWA/ODOT Section 01030, Section 01040 and Section 01120. Installed complete.		
	1	LS	\$
27	<b>Maackia Amurensis “Amur Maackia”, 6’ Height with 1.5” Caliper</b> , per approved plans, landscape documents and specifications, and APWA/ODOT Section 01030 and 01040. Includes watering bags. Installed complete and established.		
	5	EA	\$
28	<b>Pistachia Chinensis “Chinese Pistache”, 6’ Height with 1.5” Caliper</b> , per approved plans, landscape documents and specifications, and APWA/ODOT Section 01030 and 01040. Includes watering bags. Installed complete and established.		
	5	EA	\$
29	<b>Koelreuteria Paniculata “Golden Rain Tree”, 6’ Height with 1.5” Caliper</b> , per approved plans, landscape documents and specifications, and APWA/ODOT Section 01030 and 01040. Includes watering bags. Installed complete and established.		
	3	EA	\$
30	<b>Install Multiple Mailbox Support and Mailbox</b> , remove and replace existing mailboxes, per approved plans, GP100, and APWA/ODOT Section 01070. Installed complete. Temporarily mount during construction.		
	3	EA	\$
31	<b>Install Single Mailbox Supports and Mailboxes</b> , remove and replace existing mailboxes, per approved plans, GP100, and APWA/ODOT Section 01070. Installed complete. Temporarily mount during construction.		
	3	EA	\$
32	<b>Install Pedestrian Stairway with Handrails Per Detail 1 (902 NW B ST)</b> , remove and replace existing stairway, per approved plans, ODOT Standard Drawing RD770, RD771, and APWA/ODOT Section 00759 and Section 00810. Includes sawcutting, stairway removal, excavation, base rock, weep holes, installed complete.		
	1	LS	\$
33	<b>Install Pedestrian Stairway Per Detail 2 (620 NW B ST)</b> , remove and replace existing stairway, per approved plans and APWA/ODOT Section 759. Includes sawcutting, stairway removal, excavation, base rock, weep holes, installed complete.		
	1	LS	\$
34	<b>Install Pedestrian Stairway Per Detail 3 (614 NW B ST)</b> , remove and replace existing stairway, per approved plans and APWA/ODOT Section 759. Includes sawcutting, stairway removal, excavation, base rock, weep holes, installed complete.		
	1	LS	\$
35	<b>Install Pedestrian Stairway Per Detail 4 (619 NW B ST)</b> , remove and replace existing stairway, per approved plans and APWA/ODOT Section 759. Includes sawcutting, stairway removal, excavation, base rock, weep holes, installed complete.		
	1	LS	\$

<b>36</b>	<b>Install Pedestrian Stairway Per Detail 5 (613 NW B ST)</b> , remove and replace existing stairway, per approved plans and APWA/ODOT Section 759. Includes sawcutting, stairway removal, excavation, base rock, weep holes, installed complete.			
	1	LS	\$	\$
<b>37</b>	<b>Install Pedestrian Stairway Per Detail 6 (1114 NW B ST)</b> , remove and replace existing stairway, per approved plans and APWA/ODOT Section 759. Includes sawcutting, stairway removal, excavation, base rock, weep holes, installed complete.			
	1	LS	\$	\$
<b>38</b>	<b>Install Pedestrian Stairway Per Detail 7 (1111 NW B ST)</b> , remove and replace existing stairway, per approved plans and APWA/ODOT Section 759. Includes sawcutting, stairway removal, excavation, base rock, weep holes, installed complete.			
	1	LS	\$	\$
<b>39</b>	<b>Monolithic Retaining Wall</b> , monolithic concrete retaining wall at back of sidewalk, per approved plans and APWA/ODOT Section 00759. Includes excavation, backfill installed complete.			
	526	SF	\$	\$
<b>40</b>	<b>Retaining Wall with Footing</b> , monolithic concrete retaining wall at back of sidewalk, per approved plans and APWA/ODOT Section 00759. Includes excavation, backfill installed complete.			
	1,259	SF	\$	\$
<b>PART 00200 – TEMPORARY FEATURES AND APPURTENANCES</b>				\$
<b>PART 00300 – ROADWORK</b>				\$
<b>PART 00400 – DRAINAGE AND SEWERS</b>				\$
<b>PART 00600 – BASES</b>				\$
<b>PART 00700 – WEARING SURFACES</b>				\$
<b>PART 01000 – RIGHT OF WAY DEVELOPMENT AND CONTROL</b>				\$
<b>SUM OF EXTENDED TOTALS</b>				\$
<b>CONTRACTOR SIGNATURE:</b>				
<b>DATE:</b>				