

ADDENDUM NO. 1to **CONTRACT DOCUMENTS** for

“F” and 6th Street Stormwater Replacement
 Project No. DO6353
 Grants Pass, Oregon 97526

To All Plan Holders:

The following changes, additions, and/or deletions are hereby made a part of the Contract Documents for the construction of the “F” and 6th Street Stormwater Replacement, Project No. DO6353, Grants Pass, Oregon, as fully and completely as if the same were fully set forth therein:

1. ON THE CONSTRUCTION PLANS...

- On Page 2 of 4; Change note #3: Concrete Pipe is being replaced with HDPE.
- On Page 2 of 4; Change note #7: Concrete Pipe is being replaced with HDPE.

2. IN THE CONTRACT DOCUMENTS...

Bid Proposal - Bid Schedule: - The following bid items have been revised or added.

8	Install 12” Storm Drain Pipe , HDPE, per approved plans, per GP300, RD300 and APWA/ODOT Sec. 00445. Includes connection to storm drain system, trench excavation, bedding and compacted backfill per APWA/ODOT Sec.00405, installed complete.				
	<u>235</u>	LF	\$		\$
14	Asphalt Pavement, Trench Patch , ½” dense, Level 2 mix, 4” compacted thickness, per GP300 and APWA/ODOT Section 00744. Includes any minor valve or manhole adjustments. Installed complete.				
	<u>60</u>	TN	\$		\$
15	Concrete Curb & Gutter, Type “A” (Match Existing) , per approved plans, GP700 and APWA/ODOT Sec. 00759, includes excavation, curb openings per detail, installed complete.				
	<u>30</u>	LF	\$		\$
16	Concrete Sidewalk (Match Existing) , per approved plans, GP720 and APWA/ODOT Sec. 00759, includes excavation, base rock, concrete flatwork, installed complete.				
	<u>60</u>	SF	\$		\$

Note: Original bid item number 9 and 16 have been removed.

3. CLARIFICATIONS...

Revised Bid Schedule is TWO pages.

- Trench in 6th St - ODOT has waived Slurry Requirements.
- Compaction testing in trench is required.
- Match existing 9"-11" asphalt on 6th street.
- No "pour-in-place" manholes.
- Limited area for staging in Grasshopper Parking lot will be allowed. (201 NW "F" St.).
- All concrete pipe is to be HDPE.

ATTACHED ARE THE FOLLOWING:

- **REVISED PAGES OF THE BID SCHEDULE (2 PAGES)**
- PLEASE NOTE THAT BID ITEMS HAVE BEEN **RE-NUMBERED**

PLEASE USE THESE REPLACEMENT PAGES WHEN SUBMITTING YOUR BID.

All Bidders shall acknowledge receipt and acceptance of this Addendum No. 1 by signing in the space provided and submitting the signed Addendum with the bid. Bids submitted without this Addendum will be considered irregular and may not be accepted.

RECEIPT OF THIS ADDENDUM IS ACKNOWLEDGED AND CONDITIONS ARE HEREBY

AGREED TO THIS _____ DAY OF _____ 2021.

Bidder's Name (Company)

BY: _____
(Signature)

END OF ADDENDUM NO. 1

BID SCHEDULE

“F” & 6th Street Stormwater Replacement DO6353

PART 00200 – TEMPORARY FEATURES AND APPURTENANCES				
Item	Quantity	Unit	Unit Price (Fig.)	Extended Amount
1	Mobilization , move in of equipment and materials per APWA/ODOT Sec. 00210, installed, complete.			
	1	LS	\$	\$
2	Work Zone Traffic Control, includes TCD, TCM and TCP per approved plans, M.U.T.C.D., and APWA/ODOT Sec. 00225 and 00225.90 (b), complete.			
	1	LS	\$	\$
3	Erosion & Sediment Control , per approved plans and APWA/ODOT Sec. 00280.00 Inlet Protection, Dust Control, Sediment Fence, Biofilter Bags, installed complete.			
	1	LS	\$	\$
PART 00300 – ROADWORK				
4	Removal of Structures and Obstructions , includes removal and proper disposal of existing pipe, AC, curb & gutter and sidewalk and saw cutting or other methods of cutting pavement, per approved plans and APWA/ODOT Sec. 00310.and 00291.20(c), (Hazardous Waste), complete.			
	1	LS	\$	\$
5	Asphalt Pavement Cutting for “T” patch , per approved plans and APWA/ODOT Section 0000310 and City pavement cut policy.			
	1,220	LF	\$	\$
PART 00400 – DRAINAGE AND SEWERS				
6	60” Eccentric Storm Drain Manhole , per approved plans, RD335 and APWA /ODOT Sec. 00470. Includes manhole, excavation, bedding and compacted backfill per APWA/ODOT Sec. 00405, adjustment to finish grade, concrete collars and pipe connections, installed, complete.			
	1	EA	\$	\$
7	48” Flattop Storm Drain Manhole , per approved plans, GP338 and APWA /ODOT Sec. 00470. Includes manhole, excavation, bedding and compacted backfill per APWA/ODOT Sec. 00405, adjustment to finish grade, concrete collars and pipe connections, installed, complete.			
	1	EA	\$	\$
8	Install 12” Storm Drain Pipe, HDPE , per approved plans, per GP300, RD300 and APWA/ODOT Sec. 00445. Includes connection to storm drain system, trench excavation, bedding and compacted backfill per APWA/ODOT Sec.00405, installed complete.			
	235	LF	\$	\$
9	Install 6” Storm Drain Pipe, Cast Iron , per approved plans, per GP300, RD300 and APWA/ODOT Sec. 00445. Includes connection to storm drain system, trench excavation, bedding and compacted backfill per APWA/ODOT Sec.00405, installed complete.			
	10	LF	\$	\$

10	Connect Existing Storm Drain to New Storm Drain , per approved plans, and APWA/ODOT Sec. 00445. Includes all connections to existing storm drain pipe, trench excavation, bedding and compacted backfill per GP300, installed complete.
5	EA \$ \$
11	Locate Existing Storm Drain Laterals , Includes any means necessary (dewatering, TV, potholing, removal of obstructions, etc.) to determine the quantity and locations of all existing storm drain laterals connected to existing storm drain pipe, trench excavation, bedding and compacted backfill per GP300, complete.
1	LS \$ \$
12	Connect Existing Storm Drain Laterals , per approved plans, and APWA/ODOT Sec. 00445. Includes all connections to existing storm drain laterals, trench excavation, bedding and compacted backfill per GP300, installed complete. Does not include curb, gutter or sidewalk removal and replacement.
7	EA \$ \$
13	Concrete Inlet, Type "G-2M" , per GP364, approved plans and APWA/ODOT Sec. 00470. Includes excavation, backfill and all pipe connections. Installed complete.
1	EA \$ \$
PART 00700 – WEARING SURFACES	
14	Asphalt Pavement, Trench Patch, ½" dense, Level 2 mix, 4" compacted thickness , per GP300 and APWA/ODOT Section 00744. Includes any minor valve or manhole adjustments. Installed complete.
60	TN \$ \$
15	Concrete Curb & Gutter, Type "A" (Match Existing) , per approved plans, GP700 and APWA/ODOT Sec. 00759, includes excavation, curb openings per detail, installed complete.
30	LF \$ \$
16	Concrete Sidewalk (Match Existing) , per approved plans, GP720 and APWA/ODOT Sec. 00759, includes excavation, base rock, concrete flatwork, installed complete.
60	SF \$ \$

PART 00200 – TEMPORARY FEATURES AND APPURTENANCES	\$
PART 00300 – ROADWORK	\$
PART 00400 – DRAINAGE AND SEWERS	\$
PART 00700 – WEARING SURFACES	\$
SUM OF EXTENDED TOTALS	\$
CONTRACTOR SIGNATURE:	
DATE:	