

**ADDENDUM NO. 1**to **CONTRACT DOCUMENTS** for

FY'21 Sanitary Sewer Replacement Projects

Project Number: SE6375

Grants Pass, Oregon 97526

To All Plan Holders:

The following changes, additions, and/or deletions are hereby made a part of the Contract Documents for the construction of the FY'21 Sanitary Sewer Replacement Project No. SE6375, Grants Pass, Oregon, as fully and completely as if the same were fully set forth therein:

**1. IN THE CONTRACT DOCUMENTS...****Bid Proposal – Bid Schedule: - The following bid items have been revised or added.**

<b>2</b>	<b>Flagging Hours, APWA/ODOT Sec. 00225.97 (a)</b>			
	350	HRS	\$52.00	\$18,200.00
<b>4</b>	<b>Traffic Control Supervisor, TCS will oversee ALL traffic control operations on a daily basis and will be the direct contact for discussion and implementation of any traffic control issues and/or concerns for the duration of the project, per approved plans and APWA/ODOT Sec. 00225.</b>			
	1	LS	\$	\$
<b>12</b>	<b>Trench Foundation Stabilization (Full Trench Width), per GP300 and per APWA/ODOT Sec. 00331, includes 12" over excavation, installation of 12" depth backfill and compaction with 1 ½" clean, installed, complete.</b>			
	420	TN	\$	\$

**NOTE: ORIGINAL BID ITEMS HAVE BEEN RENUMBERED.****2. CLARIFICATIONS...**

- On the City of Grants Pass Website, the Bid Documents were missing The Performance and Payment Bond pages. This has been rectified.

**ATTACHED ARE THE FOLLOWING:**

- **REVISED PAGES OF THE BID SCHEDULE (4 PAGES)**
- PLEASE NOTE THAT BID ITEMS HAVE BEEN **RE-NUMBERED**
- **PLEASE USE THESE REPLACEMENT PAGES WHEN SUBMITTING YOUR BID**

All Bidders shall acknowledge receipt and acceptance of this Addendum No. 1 by signing in the space provided and submitting the signed Addendum with the bid. Bids submitted without this Addendum will be considered irregular and may not be accepted.

RECEIPT OF THIS ADDENDUM IS ACKNOWLEDGED AND CONDITIONS ARE HEREBY

AGREED TO THIS \_\_\_\_\_ DAY OF \_\_\_\_\_ 2022.

\_\_\_\_\_  
Bidder's Name (Company)

BY: \_\_\_\_\_  
(Signature)

**END OF ADDENDUM NO. 1**

**BID SCHEDULE**  
**FY '21 Sanitary Sewer Replacement Projects**  
**SE6375**

<b>PART 00200 – TEMPORARY FEATURES AND APPURTENANCES</b>				
<b>Item</b>	<b>Quantity</b>	<b>Unit</b>	<b>Unit Price (Fig.)</b>	<b>Extended Amount</b>
<b>1</b>	<b>Mobilization</b> , move in of equipment and materials per APWA/ODOT Sec. 00210, complete.			
	1	LS	\$	\$
<b>2</b>	<b>Flagging Hours</b> , APWA/ODOT Sec. 00225.97 (a)			
	350	HRS	\$52.00	\$18,200.00
<b>3</b>	<b>Work Zone Traffic Control</b> , includes TCD, TCM and TCP per approved plans, M.U.T.C.D., and APWA/ODOT Sec. 00225 and 00225.90 (b), complete.			
	1	LS	\$	\$
<b>4</b>	<b>Traffic Control Supervisor</b> , TCS will oversee ALL traffic control operations on a daily basis and will be the direct contact for discussion and implementation of any traffic control issues and/or concerns for the duration of the project, per approved plans and APWA/ODOT Sec. 00225.			
	1	LS	\$	\$
<b>5</b>	<b>Erosion &amp; Sediment Control</b> , per approved plans and APWA/ODOT Sec. 00280.00 Inlet Protection, Dust Control, Sediment Fence, Biofilter Bags, installed complete.			
	1	LS	\$	\$
<b>PART 00300 – ROADWORK</b>				
<b>6</b>	<b>Removal of Structures and Obstructions</b> , includes removal and proper disposal of existing pipe, AC, curb & gutter and sidewalk and saw cutting or other methods of cutting pavement, per approved plans and APWA/ODOT Sec. 00310 and 00291.20(c), (Hazardous Waste), complete.			
	1	LS	\$	\$
<b>7</b>	<b>Clearing and Grubbing</b> , per approved plans and APWA/ODOT Sec. 00320, including all vegetation, trees, Pacific Power wood remains and stumps marked for removal. Also included is air/pneumatic soil excavation to be performed by an ISA arborist.			
	1	LS	\$	\$
<b>8</b>	<b>Abandon and Slurry Fill Existing 6 inch Sanitary Sewer Pipe in Place</b> , Fill existing sanitary sewer main to be abandoned within the right-of-way with reduced density flowable fill per Snap-Tite Design Guide, per approved plans and APWA/ODOT Sec. 00490.43. Includes furnishing and filling pipe with slurry and plugs on ends of pipe installed complete.			
	1	LS	\$	\$
<b>9</b>	<b>General Earthwork (Excavation)</b> , per approved plans and APWA/ODOT Section 00330.			
	1	LS	\$	\$

10	<b>Subgrade Geotextile</b> , per approved plans and APWA/ODOT Sec. 00350. Installed, complete.			
	1,817	SY	\$	\$
11	<b>Asphalt Pavement Cutting for "T" patch</b> , per approved plans and APWA/ODOT Section 0000310 and City pavement cut policy.			
	4,295	LF	\$	\$
12	<b>Trench Foundation Stabilization (Full Trench Width)</b> , per GP300 and per APWA/ODOT Sec. 00331, includes 12" over excavation, installation of 12" depth backfill and compaction with 1 ½" clean, installed, complete.			
	420	TN	\$	\$
<b>PART 00400 – DRAINAGE AND SEWERS</b>				
13	<b>48" Eccentric Storm Drain Manhole</b> , per approved plans, GP338 and APWA /ODOT Sec. 00470. Includes manhole, excavation, bedding and compacted backfill per APWA/ODOT Sec. 00405, adjustment to finish grade, concrete collars and pipe connections, installed, complete.			
	1	EA	\$	\$
14	<b>48" Concentric Flattop Sewer Manhole</b> , per approved plans, GP338 and APWA /ODOT Sec. 00470. Includes manhole, excavation, bedding and compacted backfill per APWA/ODOT Sec. 00405, adjustment to finish grade, concrete collars and pipe connections, installed, complete.			
	1	EA	\$	\$
15	<b>48" Eccentric Sanitary Sewer Manhole</b> , per approved plans, GP338 and APWA /ODOT Sec. 00470. Includes manhole, excavation, bedding and compacted backfill per APWA/ODOT Sec. 00405, adjustment to finish grade, concrete collars and pipe connections, installed, complete.			
	7	EA	\$	\$
16	<b>8" Sanitary Sewer Cleanout</b> , per approved plans, GP338 and APWA /ODOT Sec. 00470. Includes cleanout, excavation, bedding and compacted backfill per APWA/ODOT Sec. 00405, adjustment to finish grade, installed, complete.			
	1	EA	\$	\$
17	<b>Install 8" Sanitary Sewer Main, PVC 3034</b> , per approved plans, per GP300 and APWA/ODOT Sec. 00445. Includes pipe, trench excavation, bedding and compacted backfill per APWA/ODOT Sec.00405, installed complete.			
	2,321	LF	\$	\$
18	<b>Install 8" Sanitary Sewer Main, PVC C900</b> , per approved plans, per GP300 and APWA/ODOT Sec. 00445. Includes pipe, trench excavation, bedding and compacted backfill per APWA/ODOT Sec.00405, installed complete.			
	62	LF	\$	\$
19	<b>4" Sanitary Sewer Lateral</b> , per approved plans and APWA/ODOT Sec. 00445. Includes, pipe, trench excavation, bedding and backfill, per GP300 and APWA/ODOT Sec. 00405, installed, complete.			
	68	EA	\$	\$
20	<b>Install 3" Storm Drain Pipe, CL. 50 Ductile Iron</b> , per approved plans and APWA/ODOT Sec. 00445. Includes connecting storm drain through the curb, pipe, trench excavation, sawcutting, concrete, bedding and compacted backfill per GP300 and APWA/ODOT Sec.00405, installed complete.			
	43	LF	\$	\$

21	<b>Install 12" Storm Drain Pipe, HDPE</b> , per approved plans and APWA/ODOT Sec. 00445. Includes trench excavation, bedding and compacted backfill per APWA/ODOT Sec.00405, installed complete.			
	156	LF	\$	\$
22	<b>Connect Existing Sanitary Sewer to New Sanitary Sewer</b> , per approved plans, and APWA/ODOT Sec. 00445. Includes all connections to existing storm drain pipe, trench excavation, bedding and compacted backfill per GP300, installed complete.			
	6	EA	\$	\$
23	<b>Connect Existing Storm Drain to New Storm Drain</b> , per approved plans and APWA/ODOT Sec. 00445. Includes all connections to existing storm drain, pipe, trench excavation, sawcutting, concrete, bedding and compacted backfill per GP300 and APWA/ODOT Sec.00405, installed complete.			
	3	EA	\$	\$
24	<b>Catch Basin, Type "G-2MA"</b> , per GP364, approved plans and APWA/ODOT Sec. 00470. Includes excavation, backfill and all pipe connections. Installed complete.			
	2	EA	\$	\$
<b>PART 00600 – BASES</b>				
25	<b>Aggregate Base Course</b> , Varying thickness of ¾"-0 aggregate, compacted in place, per approved plans and APWA/ODOT Section 00640, 00641 and 02630. Installed complete for roadway construction.			
	559	TN	\$	\$
<b>PART 00700 – WEARING SURFACES</b>				
26	<b>Asphalt Pavement</b> , ½" dense, Level 2 mix, 4" compacted thickness, per APWA/ODOT Section 00744. Includes sawcutting, pavement removal, excavation, base rock, any minor valve or manhole adjustments. Installed complete.			
	329	TN	\$	\$
27	<b>Asphalt Pavement Patch</b> , ½" dense, Level 2 mix, 4" compacted thickness, per APWA/ODOT Section 00744. Includes sawcutting, pavement removal, excavation, base rock, any minor valve or manhole adjustments. Installed complete.			
	326	TN	\$	\$
28	<b>Concrete Curb &amp; Gutter, Type "A" (Match Existing)</b> , per approved plans, GP700 and APWA/ODOT Sec. 00759. Includes sawcutting, curb and gutter removal, curb openings per detail, excavation, base rock, installed complete.			
	374	LF	\$	\$
29	<b>Concrete Curb, Type "C"</b> , per approved plans, GP700 and APWA/ODOT Sec. 00759. Includes excavation, base rock, installed complete.			
	33	LF	\$	\$
30	<b>Concrete Sidewalk</b> , per approved plans, GP720 and APWA/ODOT Sec. 00759. Includes excavation, base rock, installed complete.			
	465	SF	\$	\$
31	<b>Concrete Alley Valley Gutter</b> , per approved plans, GP702 and APWA/ODOT Sec. 00759, installed, complete.			
	1,787	SF	\$	\$

<b>32</b>	<b>Concrete Commercial Driveway Apron</b> , per approved plans, GP740, GP745, GP750 and APWA/ODOT Section 00759. Includes sawcutting, pavement removal, excavation, base rock, weep holes, installed complete.			
	1,107	SF	\$	\$
<b>33</b>	<b>Concrete Pavement</b> , per approved plans, per APWA/ODOT Section 00759. Including sawcutting, pavement removal, excavation, base rock, concrete flatwork, any minor valve or manhole adjustments, installed complete.			
	546	SF	\$	\$
<b>PART 01000 – RIGHT OF WAY DEVELOPMENT AND CONTROL</b>				
<b>34</b>	<b>Bollard</b> , per approved plans, GP130, and APWA/ODOT Section 00440. Installed complete.			
	2	EA	\$	\$
<b>35</b>	<b>Landscape Restoration</b> , restore existing landscaping, including, but not limited to imported topsoil placement, reseeding of disturbed areas and irrigation repair, per approved plans and APWA/ODOT Section 01030, Section 01040 and Section 01120. Installed complete.			
	1	LS	\$	\$
<b>36</b>	<b>Pneumatic Air Excavation</b> , per approved plans and pneumatic air excavation specifications, installed complete.			
	1	LS	\$	\$
<b>PART 00200 – TEMPORARY FEATURES AND APPURTENANCES</b>				<b>\$</b>
<b>PART 00300 – ROADWORK</b>				<b>\$</b>
<b>PART 00400 – DRAINAGE AND SEWERS</b>				<b>\$</b>
<b>PART 00600 – BASES</b>				<b>\$</b>
<b>PART 00700 – WEARING SURFACES</b>				<b>\$</b>
<b>PART 01000 – RIGHT OF WAY DEVELOPMENT AND CONTROL</b>				<b>\$</b>
<b>SUM OF EXTENDED TOTALS</b>				<b>\$</b>
<b>CONTRACTOR SIGNATURE:</b>				
<b>DATE:</b>				