

ADDENDUM NO. 1

to **CONTRACT DOCUMENTS** for

Westholm Park Playground Drainage

Project No. LB6377

Grants Pass, Oregon 97526

To All Plan Holders:

The following changes, additions, and/or deletions are hereby made a part of the Contract Documents for the construction of the Westholm Park Playground Drainage, Project No. LB6377, Grants Pass, Oregon, as fully and completely as if the same were fully set forth therein:

1. IN THE CONTRACT DOCUMENTS...

Bid Proposal - Bid Schedule: - The following bid items have been revised or added.

11	Catch Basin , per approved plans and APWA/ODOT Sec. 00470. Includes excavation, backfill and all pipe connections, installed complete.		
2	EA	\$	\$

Note: Original bid item number 11 has changed quantities from 1 to 2.

2. CLARIFICATIONS...

Revised Bid Schedule is TWO pages.

- TRACER WIRE TO BE ADDED TO ANY 4" PERFORATED PIPE, AS WELL AS ANY PIPES IN PLAYGROUND AREA.

ATTACHED ARE THE FOLLOWING:

- **REVISED PAGES OF THE BID SCHEDULE (2 PAGES)**
- PLEASE NOTE THAT BID ITEMS HAVE BEEN **REVISED**

PLEASE USE THESE REPLACEMENT PAGES WHEN SUBMITTING YOUR BID.

All Bidders shall acknowledge receipt and acceptance of this Addendum No. 1 by signing in the space provided and submitting the signed Addendum with the bid. Bids submitted without this Addendum will be considered irregular and may not be accepted.

RECEIPT OF THIS ADDENDUM IS ACKNOWLEDGED AND CONDITIONS ARE HEREBY
AGREED TO THIS _____ DAY OF _____ 2022.

Bidder's Name (Company)

BY: _____
(Signature)

END OF ADDENDUM NO. 1

BID SCHEDULE
Westholm Park Playground Drainage
LB6377

PART 00200 – TEMPORARY FEATURES AND APPURTENANCES				
Item	Quantity	Unit	Unit Price (Fig.)	Extended Amount
1	Mobilization , move in of equipment and materials per APWA/ODOT Sec. 00210, complete.			
	1	LS	\$	\$
2	Work Zone Traffic Control, includes TCD, TCM and TCP per approved plans, M.U.T.C.D., and APWA/ODOT Sec. 00225 and 00225.90 (b), complete.			
	1	LS	\$	\$
3	Erosion and Sediment Control , per approved plans and APWA/ODOT Sec. 00280.00 Inlet protection, Dust Control, Sediment Fence, Biofilter Bags etc., installed complete.			
	1	LS	\$	\$
4	Construction Staking , lay out and set construction stakes and marks to establish the lines, grades, and slopes necessary for project completion, per Special Provisions Sec. 00150.15 (c).			
	1	LS	\$	\$
PART 00300 – ROADWORK				
5	Removal of Structures and Obstructions , includes removal and proper disposal of pipe, concrete and sidewalk and sawcutting or other methods of cutting pavement, per approved plans and APWA/ODOT Sec. 00310.and 00291.20(c), (Hazardous Waste), complete.			
	1	LS	\$	\$
PART 00400 – DRAINAGE AND SEWERS				
6	48” Flat Top Storm Drain Manhole , per approved plans and GP338 and APWA /ODOT Sec. 00470. Includes manhole, excavation, bedding and compacted backfill per APWA/ODOT Sec. 00405, adjustment to finish grade and pipe connections, installed, complete.			
	1	EA	\$	\$
7	Install 8” Storm Drain Pipe, PVC 3034 , per approved plans and APWA/ODOT Sec. 00445. Includes trench excavation, bedding and compacted backfill per APWA/ODOT Sec.00405, installed complete.			
	138	LF	\$	\$
8	Install 6” Storm Drain Pipe, PVC 3034 , per approved plans and APWA/ODOT Sec. 00445. Includes trench excavation, bedding and compacted backfill per APWA/ODOT Sec.00405, installed complete.			
	80	LF	\$	\$
9	Install 4” Storm Drain Pipe, Perforated PVC 3034 , per approved plans and APWA/ODOT Sec. 00445. Includes trench excavation, bedding, compacted backfill, per APWA/ODOT Sec.00405, installed complete.			
	490	LF	\$	\$

10	Install 4" Cleanouts , per approved plans and APWA/ODOT Sec. 00445. Includes excavation, bedding and compacted backfill, per APWA/ODOT Sec.00405, installed complete.			
	13	EA	\$	\$
11	Catch Basin , per approved plans and APWA/ODOT Sec. 00470. Includes excavation, backfill and all pipe connections, installed complete.			
	2	EA	\$	\$
12	Connect Existing Storm Drain to New Storm Drain , per approved plans and APWA/ODOT Sec. 00445. Includes all connections to existing storm drain, pipe, trench excavation, sawcutting, concrete, bedding and compacted backfill per GP300 and APWA/ODOT Sec.00405, installed complete. Does not include connections to roof downspouts.			
	2	EA	\$	\$
PART 00700 – WEARING SURFACES				
13	Concrete Sidewalk (Match Existing) , per approved plans and APWA/ODOT Sec. 00759. Includes excavation, base rock, concrete flatwork, installed complete.			
	40	SF	\$	\$
PART 01000 – RIGHT OF WAY DEVELOPMENT AND CONTROL				
14	Landscape Restoration , restore existing landscaping, including, but not limited to imported topsoil placement, reseeding of disturbed areas and irrigation repair, per approved plans and APWA/ODOT Section 01030, Section 01040 and Section 01120. Installed complete.			
	1	LS	\$	\$
15	Tree Protection Fencing , per approved plans and tree protection plan specifications. Installed complete.			
	1	LS	\$	\$
16	Pneumatic Air Excavation , per approved plans and pneumatic air excavation specifications, installed complete.			
	1	LS	\$	\$
PART 00200 – TEMPORARY FEATURES AND APPURTENANCES				\$
PART 00300 – ROADWORK				\$
PART 00400 – DRAINAGE AND SEWERS				\$
PART 00700 – WEARING SURFACES				\$
PART 01000 – RIGHT OF WAY DEVELOPMENT AND CONTROL				\$
SUM OF EXTENDED TOTALS				\$
CONTRACTOR SIGNATURE:				
DATE:				