

ADDENDUM NO. 1

to **CONTRACT DOCUMENTS** for

Clyde Place Sewer and Water Main Replacement
 Project Number: SE6375
 Grants Pass, Oregon 97526

To All Plan Holders:

The following changes, additions, and/or deletions are hereby made a part of the Contract Documents for the construction of the Clyde Place Sewer and Water Main Replacement; No. SE6375, Grants Pass, Oregon, as fully and completely as if the same were fully set forth therein:

1. IN THE CONTRACT DOCUMENTS...

Bid Proposal – Bid Schedule: - The following bid items have been revised or removed.

14	Aggregate Base Course , Varying thickness of ¾"-0 aggregate, compacted in place, per approved plans and APWA/ODOT Section 00640, 00641 and 02630. Installed complete for roadway construction.		
	150	TONS	\$
23	Relocate Private Valves, RP's, DCV's etc. Behind Sidewalk , per approved plans and current plumbing code. Includes excavation.		
	1	LS	\$

NOTE: ORIGINAL BID ITEMS HAVE BEEN RENUMBERED, ITEM 14 HAS BEEN REVISED AND ITEM 23 HAS BEEN REMOVED.

2. CLARIFICATIONS...

- Bid Item # 14's quantity is increased to 150 tons of rock from 15.
- Bid Item # 23 is removed.
- Plumbing permits are to be supplied by the City, but Plumber must pick up.

ATTACHED ARE THE FOLLOWING:

- **REVISED PAGES OF THE BID SCHEDULE (3 PAGES)**
- PLEASE NOTE THAT BID ITEMS HAVE BEEN **RE-NUMBERED**
- **PLEASE USE THESE REPLACEMENT PAGES WHEN SUBMITTING YOUR BID**

All Bidders shall acknowledge receipt and acceptance of this Addendum No. 1 by signing in the space provided and submitting the signed Addendum with the bid. Bids submitted without this Addendum will be considered irregular and may not be accepted.

RECEIPT OF THIS ADDENDUM IS ACKNOWLEDGED AND CONDITIONS ARE HEREBY
AGREED TO THIS _____ DAY OF _____ 2023.

Bidder's Name (Company)

BY: _____
(Signature)

END OF ADDENDUM NO. 1

BID SCHEDULE
Clyde Place Sewer and Water Main Replacement
SE6375

PART 00200 – TEMPORARY FEATURES AND APPURTENANCES				
Item	Quantity	Unit	Unit Price (Fig.)	Extended Amount
1	Mobilization , move in of equipment and materials per APWA/ODOT Sec. 00210, complete.			
	1	LS	\$	\$
2	Work Zone Traffic Control, includes TCD, TCM, TCP, and Flagging per approved plans, M.U.T.C.D., and APWA/ODOT Sec. 00223 and 00223.90 (b), complete.			
	1	LS	\$	\$
3	Flagging , per APWA/ODOT Sec. 00223.90 (a).			
	200	HRS	\$ 57.00	\$
4	Erosion & Sediment Control , per approved plans and APWA/ODOT Sec. 00280.00 Inlet Protection, Dust Control, Sediment Fence, Biofilter Bags, installed complete.			
	1	LS	\$	\$
PART 00300 – ROADWORK				
5	Removal of Structures and Obstructions , includes removal and proper disposal of existing pipe, per approved plans and APWA/ODOT Sec. 00310.and 00291.20(c), (Hazardous Waste), complete.			
	1	LS	\$	\$
6	Asphalt Pavement Cutting , per approved plans and APWA/ODOT Section 0000310 and City pavement cut policy.			
	87	LF	\$	\$
PART 00400 – DRAINAGE AND SEWERS				
7	48” Eccentric Sanitary Sewer Manhole , per approved plans, GP338 and APWA /ODOT Sec. 00470. Includes manhole, excavation, bedding and compacted backfill per APWA/ODOT Sec. 00405, adjustment to finish grade, concrete collars and pipe connections, installed, complete.			
	1	EA	\$	\$
8	8” Sanitary Sewer Cleanout , per approved plans, GP338 and APWA /ODOT Sec. 00470. Includes cleanout, excavation, bedding and compacted backfill per APWA/ODOT Sec. 00405, adjustment to finish grade, installed, complete.			
	1	EA	\$	\$

9	Install 8" Sanitary Sewer Main, PVC 3034 , per approved plans, per GP300 and APWA/ODOT Sec. 00445. Includes pipe, trench excavation, bedding and compacted backfill per APWA/ODOT Sec.00405, installed complete.			
	369	LF	\$	\$
10	4" Sanitary Sewer Lateral, PVC , per approved plans and APWA/ODOT Sec. 00445. Includes, pipe, cleanout, Christy box, trench excavation, bedding and backfill, per GP300 and APWA/ODOT Sec. 00405, installed, complete.			
	3	EA	\$	\$
11	4" Sanitary Sewer Lateral, PVC C900 , per approved plans and APWA/ODOT Sec. 00445. Includes, pipe, cleanout, Christy box, trench excavation, bedding and backfill, per GP300 and APWA/ODOT Sec. 00405, installed, complete.			
	4	EA	\$	\$
12	Connect Existing Sanitary Sewer to New Sanitary Sewer , per approved plans, and APWA/ODOT Sec. 00445. Includes all connections to existing storm drain pipe, trench excavation, bedding and compacted backfill per GP300, installed complete.			
	1	EA	\$	\$
13	Connect New Sanitary Sewer to Existing SS Manhole , per approved plans, APWA/ODOT Sec. 00470. Includes excavation, bedding and compacted backfill, per APWA/ODOT Sec.00405, pipe connections, installed, complete.			
	1	EA	\$	\$
PART 00600 – BASES				
14	Aggregate Base Course , Varying thickness of ¾"-0 aggregate, compacted in place, per approved plans and APWA/ODOT Section 00640, 00641 and 02630. Installed complete for roadway construction.			
	150	TN	\$	\$
PART 00700 – WEARING SURFACES				
15	Asphalt Pavement , ½" dense, Level 2 mix, 3" compacted thickness, per APWA/ODOT Section 00744. Includes sawcutting, pavement removal, excavation, existing driveway behind curb, any minor valve or manhole adjustments. Installed complete.			
	275	TN	\$	\$
16	Concrete Residential Driveway Apron , per approved plans, GP740, GP745, GP750 and APWA/ODOT Section 00759. Includes sawcutting, pavement removal, excavation, base rock, weep holes, installed complete.			
	51	SF	\$	\$
17	Concrete Curb & Gutter, Type "A" (Match Existing) , per approved plans, GP700 and APWA/ODOT Sec. 00759. Includes sawcutting, curb and gutter removal, curb openings per detail, excavation, base rock, installed complete.			
	157	LF	\$	\$

PART 01000 – RIGHT OF WAY DEVELOPMENT AND CONTROL				
18	Landscape Restoration , restore existing landscaping, including, but not limited to imported topsoil placement, reseeding of disturbed areas and irrigation repair, per approved plans and APWA/ODOT Section 01030, Section 01040 and Section 01120. Installed complete.			
	1	LS	\$	\$
PART 01100 – WATER SUPPLY SYSTEMS				
19	Potable Water Service Connection, 2 Inch and Smaller , per approved plans, GP274 and APWA/ODOT Sec. 01170, installed, complete. Includes PRVs and thermal expansion tanks, installed, complete.			
	9	EA	\$	\$
20	8" Water Pipe and Fittings, Cl. 52 Ductile Iron , per approved plans and APWA/ODOT Sec. 01100. Includes pipe, tapping sleeve, fittings, valves, trench excavation, bedding and backfill per GP300 and APWA/ODOT Sec. 01100, installed, complete.			
	345	LF	\$	\$
21	Re-Plumbing to Individual Houses , as per Oregon Plumbing Specialty Code.			
	9	EA	\$	\$
22	2" Blow Off Assembly , per approved plans, GP262 and APWA/ODOT Sec. 01150, installed, complete.			
	1	EA	\$	\$
23	Fire Hydrant, Short Lead , per approved plans, GP254 and APWA/ODOT Sec. 01160. Includes excavation, backfill, connections and all appurtenances and parts necessary. Installed, complete.			
	1	EA	\$	\$
PART 00200 – TEMPORARY FEATURES AND APPURTENANCES				\$
PART 00300 – ROADWORK				\$
PART 00400 – DRAINAGE AND SEWERS				\$
PART 00600 – BASES				\$
PART 00700 – WEARING SURFACES				\$
PART 01000 – RIGHT OF WAY DEVELOPMENT AND CONTROL				\$
PART 01100 – WATER SUPPLY SYSTEMS				\$
SUM OF EXTENDED TOTALS				\$
CONTRACTOR SIGNATURE:				
DATE:				