
ADDENDUM NO. 1

to **CONTRACT DOCUMENTS** for

Portland Loo Installation - Baker Park Boating Facility
 Project No. LB6417
 Grants Pass, Oregon 97526

To All Plan Holders:

The following changes, additions, and/or deletions are hereby made a part of the Contract Documents for the construction of the Portland Loo Installation – Baker Park Boating Facility; Project No LB6417, Grants Pass, Oregon, as fully and completely as if the same were fully set forth therein:

1. ON THE CONSTRUCTION PLANS...

- The Construction Drawings have been updated to the 8-9-23 version. Previous Version was incorrect Version of plans. Download new plans here: [CONSTRUCTION DRAWINGS](#)

2. IN THE CONTRACT DOCUMENTS...

Bid Proposal - Bid Schedule: - The following bid items have been revised or added.

13	Pneumatic Air Excavation, per approved plans and pneumatic air excavation specifications, installed complete.			
	1	LS	\$	\$

Note: Bid item Number 13 added.

3. CLARIFICATIONS...

Revised Bid Schedule is THREE pages.

- Bid item 13 added to Bid Schedule.
- Plans are updated to reflect current plans.
- Notes 11 and 12 are on the correct sheets.

ATTACHED ARE THE FOLLOWING:

- **REVISED PAGES OF THE BID SCHEDULE (3 PAGES)**
- PLEASE NOTE THAT BID ITEMS HAVE BEEN **ADDED AND RE-NUMBERED**

PLEASE USE THESE REPLACEMENT PAGES WHEN SUBMITTING YOUR BID.

All Bidders shall acknowledge receipt and acceptance of this Addendum No. 1 by signing in the space provided and submitting the signed Addendum with the bid. Bids submitted without this Addendum will be considered irregular and may not be accepted.

RECEIPT OF THIS ADDENDUM IS ACKNOWLEDGED AND CONDITIONS ARE HEREBY

AGREED TO THIS _____ DAY OF _____ 2023.

Bidder's Name (Company)

BY: _____
(Signature)

END OF ADDENDUM NO. 1

BID SCHEDULE
Portland Loo Installation-Baker Park Boating Facility
LB6417

PART 00200 – TEMPORARY FEATURES AND APPURTENANCES				
Item	Quantity	Unit	Unit Price (Fig.)	Extended Amount
1	Mobilization , move in of equipment and materials per APWA/ODOT Sec. 00210, complete.			
	1	LS	\$	\$
2	Work Zone Traffic Control, includes TCD, TCM and TCP per approved plans, M.U.T.C.D., and APWA/ODOT Sec. 00225 and 00225.90 (b), complete.			
	1	LS	\$	\$
3	Erosion & Sediment Control , per approved plans and APWA/ODOT Sec. 00280.00 Inlet Protection, Dust Control, Sediment Fence, Biofilter Bags, installed complete.			
	1	LS	\$	\$
PART 00300 – ROADWORK				
4	Removal of Structures and Obstructions , includes removal and proper disposal of existing pipe, AC, curb & gutter and sidewalk and saw cutting or other methods of cutting pavement, per approved plans and APWA/ODOT Sec. 00310.and 00291.20(c), (Hazardous Waste), complete.			
	1	LS	\$	\$
5	Clearing and Grubbing , per approved plans and APWA/ODOT Sec. 00320, including all vegetation, trees, Pacific Power wood remains and stumps marked for removal. Also included is air/pneumatic soil excavation to be performed by an ISA arborist.			
	1	LS	\$	\$
6	General Earthwork (Excavation) , per approved plans and APWA/ODOT Section 00330.			
	1	LS	\$	\$
PART 00400 – DRAINAGE AND SEWERS				
7	4” Sanitary Sewer Lateral and Existing Lateral Pipe Replacement , per approved plans and APWA/ODOT Sec. 00445. Includes, pipe, pipe connections, trench excavation, bedding and backfill, per GP300 and APWA/ODOT Sec. 00405, installed, complete.			
	1	EA	\$	\$

8	4" Sanitary Sewer Cleanout , per approved plans, GP338 and APWA /ODOT Sec. 00470. Includes cleanout, excavation, bedding and compacted backfill per APWA/ODOT Sec. 00405, adjustment to finish grade, installed, complete.			
	1	EA	\$	\$
9	Floor Drain , per approved plans and APWA/ODOT Sec. 00470. Includes pipe, floor drain, excavation, backfill and all pipe connections. Installed complete.			
	1	EA	\$	\$
PART 00700 – WEARING SURFACES				
10	Concrete Sidewalk , per approved plans, GP720 and APWA/ODOT Sec. 00759. Includes excavation, base rock, installed complete.			
	445	SF	\$	\$
11	Concrete Slab (11.5" Thickness) , per approved plans, and APWA/ODOT Sec. 00759. Includes excavation, base rock, installed, complete.			
	74	SF	\$	\$
PART 01000 – RIGHT OF WAY DEVELOPMENT AND CONTROL				
12	Landscape Restoration , restore existing landscaping, including, but not limited to imported topsoil placement, reseeding of disturbed areas and irrigation repair, per approved plans and APWA/ODOT Section 01030, Section 01040 and Section 01120. Installed complete.			
	1	LS	\$	\$
13	Pneumatic Air Excavation, per approved plans and pneumatic air excavation specifications, installed complete.			
	1	LS	\$	\$
14	Power to Portland Loo , design/build and per approved plans, APWA/ODOT Sections 00960 and 00962. Includes trenching, conduit, wiring, and appurtenances per plans to provide power to Portland Loo. Installed, complete.			
	1	LS	\$	\$
15	Portland Loo Installation , per approved plans and manufacturers recommendations, installed complete. Portland Loo supplied by City of Grants Pass. Contractor to pick up and deliver to site from a pre-determined location.			
	1	EA	\$	\$
PART 01100 – WATER SUPPLY SYSTEMS				
16	1.5 Inch Water Service , per approved plans and APWA /ODOT Sec. 01100. Includes pipe, fittings, valves, trench excavation, bedding and backfill per GP300 and APWA/ODOT Sec. 01100, installed, complete.			
	400	LF	\$	\$

PART 00200 – TEMPORARY FEATURES AND APPURTENANCES	\$
PART 00300 – ROADWORK	\$
PART 00400 – DRAINAGE AND SEWERS	\$
PART 00700 – WEARING SURFACES	\$
PART 01000 – RIGHT OF WAY DEVELOPMENT AND CONTROL	\$
PART 01100 – WATER SUPPLY SYSTEMS	\$
SUM OF EXTENDED TOTALS	\$
CONTRACTOR SIGNATURE:	
DATE:	